

Port of Port Townsend

ADDENDUM NO.3

Quilcene Herb Beck Marina Boat Ramp Replacement

Port of Port Townsend Project No.: QC-01-016

Washington State Recreation and Conservation Office (RCO)

Project No. 22-2095D

TO ALL BIDDERS:

The following modifications to the bidding documents for the above-named project as originally issued on August 3, 2026 are hereby incorporated into said documents and shall be fully considered in preparation of proposals.

Please thoroughly review the Addendum.

Revise Item 9 in Specification Section 01 20 00, Measurement and Payment, Paragraph 1.05(A) as follows (added language is underlined):

9. Bid Item A9 – Cast-in-Place Access Wedge & Approach

- a. Measurement: Lump Sum (LS)
- b. Description: Work under this item shall include all materials, supplies, equipment, and labor required for fabricating, constructing, and installing the boat launch as required by the Contract Documents. Work elements for this item include but are not limited to:
 - 1) Cast-in-Place Concrete for the Access Wedge and Approach and associated items including but not limited to the following:
 - 2) Reinforcement Bar
 - 3) Excavation, Upland Stockpile
 - 4) Monument/plaque installation
 - 5) Quarry Spalls
 - 6) Crushed Surfacing Top Course (CSTC)
 - 7) Approach Wedge Hinge
 - 8) Geotextile Fabric
- c. Payment: “Cast-in-Place Access Wedge & Approach” per Lump Sum shall be full pay for all costs to complete the Cast-in-Place Access Wedge and Approach Work required by

the Contract Documents. Payment will be made based on a Lump Sum Breakdown of the "Cast-in-Place Access Wedge & Approach" item submitted by Contractor and approved by the Contracting Agency.

Revise Specification Section 03 45 33, Precast Structural Concrete, as follows (deleted language is indicated by ~~strikeout~~; additions are underlined):

1.4 QUALITY ASSURANCE

A. Qualifications

1. Manufacturer Qualifications: PCI MNL-116. Plants must be certified by the PCI Plant Certification Program for Category C1 work or be certified by the National Precast Concrete Association. At the Contracting Agency 's option, concrete plant quality control program records must be available for review.

~~2. Installer Certification: Precast concrete erector with erecting organization and all erecting crews certified and designated by PCI's Certificate of Compliance to erect Category S1 (Simple Structural Systems).~~

2.3. Testing Agency Qualifications: Qualified according to ASTM C1077 and ASTM E329 for testing indicated.



Digitally signed by David K. Nakagawara
DN: C=US, E=dnakagawara@portoftpt.com,
O=Port of Port Townsend,
OU=Engineering, CN=David K. Nakagawara
Reason: I am the author of this document
Date: 2026.09.17 13:36:20 -0700

Addendum issued by: _____